167

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
17	260.43	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of **ready mixed concrete for RCC works** laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - **Ground Floor**	Cum	**6742.44**	Rupees Six Thousand Seven Hundred FourtyTwo Paise FourtyFour Only
18	114.46	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of **ready mixed concrete for RCC works** laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - **First Floor**	Cum	**6742.44**	Rupees Six Thousand Seven Hundred FourtyTwo Paise FourtyFour Only
19	114.46	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of **ready mixed concrete for RCC works** laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - **Second Floor**	Cum	**6742.44**	Rupees Six Thousand Seven Hundred FourtyTwo Paise FourtyFour Only
20	123.46	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of **ready mixed concrete for RCC works** laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - **Third Floor**	Cum	**6742.44**	Rupees Six Thousand Seven Hundred FourtyTwo Paise FourtyFour Only
21	9.98	Providing and laying cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of **ready mixed concrete for RCC works** laid in 15 cm thick layers and well compacted including vibrating curing etc., with all lead and lift etc., complete. (exculsive of cost of steel and fabrication charges) - **Terrace Floor**	Cum	**6742.44**	Rupees Six Thousand Seven Hundred FourtyTwo Paise FourtyFour Only
22	478.40	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for **Foundation , footing ,** bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2	Sqmt	**249.48**	Rupees Two Hundred FourtyNine Paise FourtyEight Only
23	1082.00	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of **beams,** beam hauncing cantilever girders, bressumers & **lintels** & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - **Ground Floor**	Sqmt	**276.48**	Rupees Two Hundred SeventySix Paise FourtyEight Only
24	467.00	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of **beams,** beam hauncing cantilever girders, bressumers & **lintels** & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - **First Floor**	Sqmt	**281.88**	Rupees Two Hundred EightyOne Paise EightyEight Only
25	344.50	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of **beams,** beam hauncing cantilever girders, bressumers & **lintels** & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - **Second Floor**	Sqmt	**287.28**	Rupees Two Hundred EightySeven Paise TwentyEight Only
26	344.50	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of **beams,** beam hauncing cantilever girders, bressumers & **lintels** & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - **Third Floor**	Sqmt	**292.68**	Rupees Two Hundred NinetyTwo Paise SixtyEight Only

"DTS Approved"

Executive Engineer

Contractor

C.E (R.R.N.)

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
27	24.90	Providing and removing centering, shuttering, strutting, propping etc., an removal of form work for sides & soffits of **beams,** beam hauncing cantilever girders, bressumers & **lintels** & not exceeding 1.0 in depth including cost of all materials, labour complete as per specifications - **Terrace Floor**	Sqmt	**298.08**	Rupees Two Hundred NinetyEight Paise Eight Only
28	394.80	Providing and removing centering, shuttering, strutting, propping etc., for **columns**, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - **Ground Floor**	Sqmt	**395.28**	Rupees Three Hundred NinetyFive Paise TwentyEight Only
29	238.60	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - **First Floor**	Sqmt	**400.68**	Rupees Four Hundred Paise SixtyEight Only
30	174.80	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - **Second floor**	Sqmt	**406.08**	Rupees Four Hundred Six Paise Eight Only
31	174.80	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - **Second floor**	Sqmt	**411.48**	Rupees Four Hundred Eleven Paise FourtyEight Only.
32	30.40	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specification. - **Terrace floor**	Sqmt	**416.88**	Rupees Four Hundred Sixteen Paise EightyEight Only
33	592.10	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - **Ground Floor**	Sqmt	**594.00**	Rupees Five Hundred NinetyFour Only
34	567.70	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - **First Floor**	Sqmt	**594.00**	Rupees Five Hundred NinetyFour Only
35	452.70	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - **Second Floor**	Sqmt	**594.00**	Rupees Five Hundred NinetyFour Only
36	535.00	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - **Third Floor**	Sqmt	**594.00**	Rupees Five Hundred NinetyFour Only
37	34.70	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications. Specification upto 3.5 m from Ground level - **Terrace Floor**	Sqmt	**594.00**	Rupees Five Hundred NinetyFour Only

"DTS Approved"

Executive Engineer

Contractor

(B.B.N.)

165

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
38	45.30	Providing and removing centering, shuttering, strutting, propping etc., **for edges of slabs** and breaks in floor including cost of all materials, labour complete as per specifications - **Ground Floor**	Sqmt	**732.24**	Rupees Seven Hundred ThirtyTwo Paise TwentyFour Only
39	29.90	Providing and removing centering, shuttering, strutting, propping etc., **for edges of slabs** and breaks in floor including cost of all materials, labour complete as per specifications - **First Floor**	Sqmt	**737.64**	Rupees Seven Hundred ThirtySeven Paise SixtyFour Only
40	23.10	Providing and removing centering, shuttering, strutting, propping etc., **for edges of slabs** and breaks in floor including cost of all materials, labour complete as per specifications - **Second Floor**	Sqmt	**743.04**	Rupees Seven Hundred FourtyThree Paise Four Only
41	23.10	Providing and removing centering, shuttering, strutting, propping etc., **for edges of slabs** and breaks in floor including cost of all materials, labour complete as per specifications - **Third Floor**	Sqmt	**748.44**	Rupees Seven Hundred FourtyEight Paise FourtyFour Only
42	2.70	Providing and removing centering, shuttering, strutting, propping etc., **for edges of slabs** and breaks in floor including cost of all materials, labour complete as per specifications - **Terrace Floor**	Sqmt	**753.84**	Rupees Seven Hundred FiftyThree Paise EightyFour Only
43	28.50	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. **Ground Floor**	Sqmt	**513.00**	Rupees Five Hundred Thirteen Only
44	28.50	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. **First Floor**	Sqmt	**518.40**	Rupees Five Hundred Eighteen Paise Fourty Only
45	22.80	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. **Second Floor**	Sqmt	**523.80**	Rupees Five Hundred TwentyThree Paise Eighty Only
46	22.80	Providing and removing centring, shuttering, strutting, proping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials,labour complete as per specification and directed by the Engineer in Charge. **Third Floor**	Sqmt	**529.20**	Rupees Five Hundred TwentyNine Paise Twenty Only
47	36.60	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted **plain chajja 7.50 Cms** avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. **Ground Floor**	Sqmt	**492.48**	Rupees Four Hundred NinetyTwo Paise FourtyEight Only

"DTS Approved"

C.E (R.R.N.)

Contractor

Executive Engineer

16th

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
48	37.70	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted **plain chajja 7.50 Cms** avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. **First Floor**	Sqmt	**497.88**	Rupees Four Hundred NinetySeven Paise EightyEight Only
49	15.70	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted **plain chajja 7.50 Cms** avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. **Second Floor**	Sqmt	**503.28**	Rupees Five Hundred Three Paise TwentyEight Only
50	15.70	Providing and laying in position reinforced cement cocnrete of design mix M20 with OPC cement @ 27.20 Kgs with 12mm & down sizes graded grantie metal coarse aggregated @ 0.5865 cum & fine aggregates, @ 0.391 Cum with super super plastisiser @ 0.225 Ltrs maichine mixed well compacted **plain chajja 7.50 Cms** avg thickness, up to ground floor level including removing centering, shuttering, strutting, propping etc., and removal of form work for cost of all materials, laobur HOM of machinary, curing complete as per specification. **Third Floor**	Sqmt	**508.68**	Rupees Five Hundred Eight Paise SixtyEight Only
51	37.00	Providing and **removing centering,** shuttering, strutting, propping etc., for **chajjas**, corbels of all shapes & sizes, at all elevations & heights. **Ground Floor**	Sqmt	**291.60**	Rupees Two Hundred NinetyOne Paise Sixty Only
52	38.00	Providing and **removing centering,** shuttering, strutting, propping etc., for **chajjas**, corbels of all shapes & sizes, at all elevations & heights. **First Floor**	Sqmt	**297.00**	Rupees Two Hundred NinetySeven Only
53	16.00	Providing and **removing centering,** shuttering, strutting, propping etc., for **chajjas**, corbels of all shapes & sizes, at all elevations & heights. **Second Floor**	Sqmt	**302.40**	Rupees Three Hundred Two Paise Fourty Only
54	16.00	Providing and **removing centering,** shuttering, strutting, propping etc., for **chajjas**, corbels of all shapes & sizes, at all elevations & heights. **Third Floor**	Sqmt	**307.80**	Rupees Three Hundred Seven Paise Eighty Only
55	170.00	Extra For providing throating or **drip moulding to RCC chajjas** with plastreing(labour charges only), as perspecification - **Ground Floor**	Rmt	**21.60**	Rupees TwentyOne Paise Sixty Only
56	47.00	Extra For providing throating or **drip moulding to RCC chajjas** with plastreing(labour charges only), as perspecification - **First Floor**	Rmt	**21.60**	Rupees TwentyOne Paise Sixty Only
57	47.00	Extra For providing throating or **drip moulding to RCC chajjas** with plastreing(labour charges only), as perspecification - **Second Floor**	Rmt	**21.60**	Rupees TwentyOne Paise Sixty Only
58	47.00	Extra For providing throating or **drip moulding to RCC chajjas** with plastreing(labour charges only), as perspecification - **Third Floor**	Rmt	**21.60**	Rupees TwentyOne Paise Sixty Only

"DTS Approved"

Contractor

C.E (R.R.N.)

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
59	158.00	Providing **lath plastering** cement mortor 1:3, 5 Cm thick with 6 mm dia mild steel @ 20 cm c/c both hiorizantaly & Vertically fixing Chicken Mesh for drop chejja , facia, Backing to cupboard including cost of all materials, labour, providing & removing form work H O M of Machinery , curing, complete as per specifications.	Sqmt	**1044.36**	Rupees One Thousand FourtyFour Paise ThirtySix Only
60	50.00	Providing **TMT Steel reinforcement** for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. **FOR TMT Bars Fe- 500 - Ground Floor**	Tonne	**65455.56**	Rupees SixtyFive Thousand Four Hundred FiftyFive Paise FiftySix Only
61	22.00	Providing **TMT Steel reinforcement** for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. **FOR TMT Bars Fe- 500 - First Floor**	Tonne	**65965.32**	Rupees SixtyFive Thousand Nine Hundred SixtyFive Paise ThirtyTwo Only
62	17.80	Providing **TMT Steel reinforcement** for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. **FOR TMT Bars Fe- 500 - Second floor**	Tonne	**66475.08**	Rupees SixtySix Thousand Four Hundred SeventyFive Paise Eight Only
63	17.80	Providing **TMT Steel reinforcement** for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. **FOR TMT Bars Fe- 500 - Third Floor**	Tonne	**66984.84**	Rupees SixtySix Thousand Nine Hundred EightyFour Paise EightyFour Only
64	1.50	Providing **TMT Steel reinforcement** for RCC works including straightening, cutting, bending, hooking, placing in position lapping and / or welding wherever required, tieng with binding wire and anchoring to the adjoining members wherever necessary, complete as per design (laps, hooks and wastage shall not be measured and paid) cost of all materials, labour, HOM of machineries etc., complete as per specifications. Specification No.KBS 4.6.3. **FOR TMT Bars Fe- 500 - Terrace Floor**	Tonne	**67494.60**	Rupees SixtySeven Thousand Four Hundred NinetyFour Paise Sixty Only
65	161.40	KSRB-5.2-2: Providing and constructing granite / trap / basalt **size stone masonry** in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	**5668.92**	Rupees Five Thousand Six Hundred SixtyEight Paise NinetyTwo Only

"DTS Approved"

C.E (R.R.N.)

Executive Engineer

Contractor

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
66	103.90	Providing and constructing **burnt brick masonry** with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - **Ground Floor**	Cum	7328.88	Rupees Seven Thousand Three Hundred TwentyEight Paise EightyEight Only
67	77.20	Providing and constructing **burnt brick masonry** with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - **First Floor**	Cum	7382.88	Rupees Seven Thousand Three Hundred EightyTwo Paise EightyEight Only
68	77.20	Providing and constructing **burnt brick masonry** with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - **Second Floor**	Cum	7436.88	Rupees Seven Thousand Four Hundred ThirtySix Paise EightyEight Only
69	77.20	Providing and constructing **burnt brick masonry** with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - **Third Floor**	Cum	7490.88	Rupees Seven Thousand Four Hundred Ninety Paise EightyEight Only
70	41.60	Providing and constructing **burnt brick masonry** with approved quality of modular bricks of standard size of class designation 5.0 newton per sq mm (table moulded) with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. - **Terracę Floor**	Cum	7544.88	Rupees Seven Thousand Five Hundred FourtyFour Paise EightyEight Only
71	120.30	Construction of **partition wall 11.2 cms thick** with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with **cement mortar** 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - **Ground Floor**	Sqmt	1007.64	Rupees One Thousand Seven Paise SixtyFour Only
72	79.80	Construction of **partition wall 11.2 cms thick** with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with **cement mortar** 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - **First Floor**	Sqmt	1013.04	Rupees One Thousand Thirteen Paise Four Only
73	79.80	Construction of **partition wall 11.2 cms thick** with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with **cement mortar** 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - **Second Floor**	Sqmt	1018.44	Rupees One Thousand Eighteen Paise FourtyFour Only
74	79.80	Construction of **partition wall 11.2 cms thick** with non modular table moulded burnt bricks of class designation 5.0Newton per Sqmm with **cement mortar** 1:4 including cost of materials, labour charges, scaffolding, curing complete as per specifications. Specification No. KBS 6.2- KSRB 6-7.2 : - do - with bricks of class designation 5.0 Newton per sqm - **Third Floor**	Sqmt	1023.84	Rupees One Thousand TwentyThree Paise EightyFour Only

"DTS Approved"

Executive Engineer

Contractor

C.E (R.R.N.)

161

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
75	356.40	Providing and constructing load bearing wall with **solid concrete blocks** having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm **- Ground Floor**	Sqmt	**1011.96**	Rupees One Thousand Eleven Paise NinetySix Only
76	98.90	Providing and constructing load bearing wall with **solid concrete blocks** having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm **-First Floor**	Sqmt	**1044.36**	Rupees One Thousand FourtyFour Paise ThirtySix Only
77	45.00	Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 5.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4 - do - with solid concrete blocks of size 400x200x200mm -Second Floor	Sqmt	**1076.76**	Rupees One Thousand SeventySix Paise SeventySix Only
78	105.10	Construction of partition wall 10cm thick with table moulded modular burnt bricks of class designation 5.0netwon per sqmm with cemet mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped gelvanisediron of nominal thickness 0.35mm.100mm.labour charges' scaffolding' curing complete as per specification - Ground Floor	Sqmt	**851.04**	Rupees Eight Hundred FiftyOne Paise Four Only
79	104.90	Construction of partition wall 10cm thick with table moulded modular burnt bricks of class designation 5.0netwon per sqmm with cemet mortar 1:4 including providing and fixing plaster mesh manufactured out of hot dipped gelvanisediron of nominal thickness 0.35mm.100mm.labour charges' scaffolding' curing complete as per specification - First Floor	Sqmt	**856.44**	Rupees Eight Hundred FiftySix Paise FourtyFour Only
80	1161.38	Providing **18mm thick cement plaster** in single coat with cement **mortor 1:3** to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**External Plastering - Ground Floor**	Sqmt	**263.52**	Rupees Two Hundred SixtyThree Paise FiftyTwo Only
81	417.30	Providing **18mm thick cement plaster** in single coat with cement **mortor 1:3** to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**External Plastering - First Floor**	Sqmt	**263.52**	Rupees Two Hundred SixtyThree Paise FiftyTwo Only
82	384.80	Providing **18mm thick cement plaster** in single coat with cement **mortor 1:3** to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**External Plastering - Second Floor**	Sqmt	**263.52**	Rupees Two Hundred SixtyThree Paise FiftyTwo Only

" DTS Approved "

Executive Engineer

Contractor

C.E (R.R.N.)

160

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
83	276.80	Providing **18mm thick cement plaster** in single coat with cement **mortor 1:3** to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**External Plastering - Third Floor**	Sqmt	**263.52**	Rupees Two Hundred SixtyThree Paise FiftyTwo Only
84	242.00	Providing **18mm thick cement plaster** in single coat with cement **mortor 1:3** to Brick masonary including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**External Plastering - Terrace Floor**	Sqmt	**263.52**	Rupees Two Hundred SixtyThree Paise FiftyTwo Only
85	1475.22	Providing **15mm thick cement plaster** in single coat with cement mortor **1:4, to brick masonry** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(**internal) - Ground Floor**	Sqmt	**241.92**	Rupees Two Hundred FourtyOne Paise NinetyTwo Only
86	910.00	Providing **15mm thick cement plaster** in single coat with cement mortor **1:4, to brick masonry** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(**internal) - First Floor**	Sqmt	**247.32**	Rupees Two Hundred FourtySeven Paise ThirtyTwo Only
87	605.00	Providing **15mm thick cement plaster** in single coat with cement mortor **1:4, to brick masonry** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(**internal) - Second Floor**	Sqmt	**252.72**	Rupees Two Hundred FiftyTwo Paise SeventyTwo Only
88	605.00	Providing **15mm thick cement plaster** in single coat with cement mortor **1:4, to brick masonry** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(**internal) - Third Floor**	Sqmt	**258.12**	Rupees Two Hundred FiftyEight Paise Twelve Only
89	79.00	Providing **15mm thick cement plaster** in single coat with cement mortor **1:4, to brick masonry** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.(**internal) - Terrace Floor**	Sqmt	**258.12**	Rupees Two Hundred FiftyEight Paise Twelve Only
90	932.20	Providing **12mm thick cement plaster in single coat** with cement mortor 1:3, to **ceiling** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - **Ground floor**	Sqmt	**228.96**	Rupees Two Hundred TwentyEight Paise NinetySix Only
91	640.00	Providing **12mm thick cement plaster in single coat** with cement mortor 1:3, to **ceiling** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - First **floor**	Sqmt	**234.36**	Rupees Two Hundred ThirtyFour Paise ThirtySix Only
92	548.00	Providing **12mm thick cement plaster in single coat** with cement mortor 1:3, to **ceiling** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Second **floor**	Sqmt	**239.76**	Rupees Two Hundred ThirtyNine Paise SeventySix Only

"DTS Approved"

Contractor

C.E (R.R.N.)

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
93	548.00	Providing **12mm thick cement plaster in single coat** with cement mortor 1:3, to **ceiling** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Third **floor**	Sqmt	**245.16**	Rupees Two Hundred FourtyFive Paise Sixteen Only
94	23.64	Providing **12mm thick cement plaster in single coat** with cement mortor 1:3, to **ceiling** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications - Terrace **floor**	Sqmt	**250.56**	Rupees Two Hundred Fifty Paise FiftySix Only
95	201.00	Providing **rough cement plastering 15 mm thick** in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications **- Ground Floor**	Sqmt	**169.56**	Rupees One Hundred SixtyNine Paise FiftySix Only
96	91.00	Providing **rough cement plastering 15 mm thick** in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications **- First Floor**	Sqmt	**174.96**	Rupees One Hundred SeventyFour Paise NinetySix Only
97	91.00	Providing **rough cement plastering 15 mm thick** in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications **- Second Floor**	Sqmt	**180.36**	Rupees One Hundred Eighty Paise ThirtySix Only
98	91.00	Providing **rough cement plastering 15 mm thick** in single coat with cement mortor 1:4, to brick masanary for base of dadooing works with sand of approved quality, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications **- Third Floor**	Sqmt	**185.76**	Rupees One Hundred EightyFive Paise SeventySix Only
99	28.00	Providing **20mm thick cement plaster** in single coat with cement mortor 1:3, to **Stone masonary & concrete Surface** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**- First Floor**	Sqmt	**285.12**	Rupees Two Hundred EightyFive Paise Twelve Only
100	28.00	Providing **20mm thick cement plaster** in single coat with cement mortor 1:3, to **Stone masonary & concrete Surface** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**- Second Floor**	Sqmt	**290.52**	Rupees Two Hundred Ninety Paise FiftyTwo Only
101	28.00	Providing **20mm thick cement plaster** in single coat with cement mortor 1:3, to **Stone masonary & concrete Surface** including rounding off corners wherver required smooth rendering,: Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.**- Third Floor**	Sqmt	**295.92**	Rupees Two Hundred NinetyFive Paise NinetyTwo Only
102	350.00	KSRB 15.8.2 Providing and fixing **plaster mesh 150mm** wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment)	Rmtr	**38.88**	Rupees ThirtyEight Paise EightyEight Only

"DTS Approved"

Contractor

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
103	380.00	KSRB 15.8.2 Providing and fixing **plaster mesh 200mm** wide manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along route of walls chipped for services, junction between RCC and brick walls including cost of materials, labour for fixing complete as per specifications. (length of mesh only be measured for payment)	Rmtr	**46.44**	Rupees FourtySix Paise FourtyFour Only
104	49.00	KSRB 15.9 Providing and fixing **Corner beads 45x45mm** size manufactured out of hot dipped galvanised iron of nominal thickness 0.35mm with a zinc coating of 120gms per sqm width, along exposed corners of walls, coloumns, lintels including cost of materials, labour for fixing complete . (length of mesh be measured for payment)	Rmtr	**28.08**	Rupees TwentyEight Paise Eight Only
105	6221.20	Providing & applying **Two coats of wall putty** to inside plasterd walls and ceiling using white cement putty. Scrapping and levelling the surface using steel blade and preparing the surface even and smooth by using different grade sand papers, including cost of materials , cost of labour and scafolding etc complete as per specifications - **For All Floors**	Sqmt	**60.48**	Rupees Sixty Paise FourtyEight Only
106	1634.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on **wall surface** to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer **- Ground Floor**	Sqmt	**97.20**	Rupees NinetySeven Paise Twenty Only
107	605.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on **wall surface** to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer **- First Floor**	Sqmt	**97.20**	Rupees NinetySeven Paise Twenty Only
108	605.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on **wall surface** to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer **- Second Floor**	Sqmt	**97.20**	Rupees NinetySeven Paise Twenty Only
109	605.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on **wall surface** to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer **- Third Floor**	Sqmt	**97.20**	Rupees NinetySeven Paise Twenty Only
110	79.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on **wall surface** to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer **- Terrace Floor**	Sqmt	**97.20**	Rupees NinetySeven Paise Twenty Only

" DTS Approved "

C.E (R.R.N.)

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
111	1637.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15 15.1 for painting two coats with plastic emulsion paint of approved brand and shade **on ceiling and / or sloping roof** as per specifications.**-Ground Floor**	Sqmt	**101.52**	Rupees One Hundred One Paise FiftyTwo Only
112	548.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15 15.1 for painting two coats with plastic emulsion paint of approved brand and shade **on ceiling and / or sloping roof** as per specifications. **-First Floor**	Sqmt	**101.52**	Rupees One Hundred One Paise FiftyTwo Only
113	548.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15 15.1 for painting two coats with plastic emulsion paint of approved brand and shade **on ceiling and / or sloping roof** as per specifications.**-Second Floor**	Sqmt	**101.52**	Rupees One Hundred One Paise FiftyTwo Only
114	548.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15 15.1 for painting two coats with plastic emulsion paint of approved brand and shade **on ceiling and / or sloping roof** as per specifications. **-Third Floor**	Sqmt	**101.52**	Rupees One Hundred One Paise FiftyTwo Only
115	24.00	Providing & applying Painting in in two coats with **plastic emulsion paint** of approved brand on wall surface to give an even approved shade after thouroughly brushing the surface free from morter drops and other forign mater including preparing the surface even and sand paer smooth, cost of materials, labour complete asper specifications with a) Primer : Extra over Item 15 15.1 for painting two coats with plastic emulsion paint of approved brand and shade **on ceiling and / or sloping roof** as per specifications. **-Terrace Floor**	Sqmt	**101.52**	Rupees One Hundred One Paise FiftyTwo Only

" DTS Approved"

C.E (R.R.N.)

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
116	350.00	Providing **Textured paint** of approved quality, colour and shade to wall surface after cleaning and rubbing the wall surface with wire brush of medium size emery stone to remove all the loosely adhering particles, the surface is then cleaned with water and ensured that it is in line and level. The textured material is then mixed with 40-50% of clean water until a homogeneous thick slurry is formed, the slurry is left for 5-10 min, to react completely with ingredients. The textured finish prepared as above is then applied to the wall surface with suitable roller/spray gun/putty/ blade / trowel to get the desired finish. The finished surface shall be applied with two coats of exterior paint of approved shade. The rate includes providing and removing scaffolding, all lead and lift and all other incidental charges etc., complete as per directions of the Engineer-in-charge of the work.	Sqmt	**382.32**	Rupees Three Hundred EightyTwo Paise ThirtyTwo Only
117	1164.00	Providing & finishing external walls in two coats over one coat of 100 % **acrylic silcon glazed primer with Antifungal paint for top coat** of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - **Ground Floor**	Sqmt	**166.32**	Rupees One Hundred SixtySix Paise ThirtyTwo Only
118	417.80	Providing & finishing external walls in two coats over one coat of 100 % **acrylic silcon glazed primer with Antifungal paint for top coat** of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - **First Floor**	Sqmt	**169.56**	Rupees One Hundred SixtyNine Paise FiftySix Only
119	385.00	Providing & finishing external walls in two coats over one coat of 100 % **acrylic silcon glazed primer with Antifungal paint for top coat** of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - **Second Floor**	Sqmt	**172.80**	Rupees One Hundred SeventyTwo Paise Eighty Only
120	277.00	Providing & finishing external walls in two coats over one coat of 100 % **acrylic silcon glazed primer with Antifungal paint for top coat** of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - **Third Floor**	Sqmt	**176.04**	Rupees One Hundred SeventySix Paise Four Only
121	242.00	Providing & finishing external walls in two coats over one coat of 100 % **acrylic silcon glazed primer with Antifungal paint for top coat** of Approved brand and shade to give an even shade after thourghly brooming the surfacfe to remove all dirt and loose powdered material, free from morter drops and and other foreign matter , cost of materails , labour, complete as per specifications - **Terrace Floor**	Sqmt	**179.28**	Rupees One Hundred SeventyNine Paise TwentyEight Only
122	19.00	Providing **Melamine polishing of approved shade** including removing and refixing of doors shutters scraping with blade and rubbing with zero size sand paper and applying sealer coat by way of spraying with necessary compressor and applying patty after rubbing with steel wool including two coats of approved shade of Melamine polish etc., complete.	Sqmt	**778.68**	Rupees Seven Hundred SeventyEight Paise SixtyEight Only

"DTS Approved"

Executive Engineer

Contractor

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
123	71.00	KSRB 15-17.5 : Applying **priming coat over new wood surface** and / or wood based surface after preparing the surface after throughly cleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, complete as per specifications.	Sqmt	**44.28**	Rupees FourtyFour Paise TwentyEight Only
124	70.80	Providing and applying **painting two coats on new wood surface and/ or wood** based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foregn matter, sand papering including cost of materials, labour complete as per specifications.	Sqmt	**90.72**	Rupees Ninety Paise SeventyTwo Only
125	510.80	KSRB 15-18.1 : Applying **Red lead ready mix priming coat over new steel** or other metal surface including preparing the surface after throughly cleaning oil, grease, dirt and other foreign matter, and scoured with wire brushes, fine steel wool, sand papers including cost of materials, labour, complete as per specifications.	Sqmt	**31.32**	Rupees ThirtyOne Paise ThirtyTwo Only
126	510.80	KSRB 15-18.2 : Providing and applying **enamel metal paint two coats** (excluding priming coat) over **new steel or other metal surface** brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications.	Sqmt	**88.56**	Rupees EightyEight Paise FiftySix Only
127	14.00	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 **- Ground Floor**	Sqmt	**2042.28**	Rupees Two Thousand FourtyTwo Paise TwentyEight Only
128	9.10	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 - **First Floor**	Sqmt	**2043.90**	Rupees Two Thousand FourtyThree Paise Ninety Only
129	9.10	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 - **Second Floor**	Sqmt	**2045.52**	Rupees Two Thousand FourtyFive Paise FiftyTwo Only
130	9.10	Providing and fixing for flooring 40mm thick sadarhalli grey flammed granite slab for bath areas in Bathrooms over a bed of 25mm thick CM 1:6 and fixing granite slab with CM 1:3 **- Third Floor**	Sqmt	**2047.14**	Rupees Two Thousand FourtySeven Paise Fourteen Only
131	24.50	Providing and laying flooring and steps fine dressed granite stone slabs 40 mm thick on cement mortar bed 1:6, 25 mm thick, and pointed with cement mortar 1:3 over existing cement concrete bed, including cost of materials, mortar, labour, curing complete as per specifications. S	Sqmt	**3413.88**	Rupees Three Thousand Four Hundred Thirteen Paise EightyEight Only
132	139.10	Flooring with 20 mm thick polished shahabad slabs using cement mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing complete as per specifications.	Sqmt	**1294.92**	Rupees One Thousand Two Hundred NinetyFour Paise NinetyTwo Only
133	102.30	Providing and laying **Hassan Green granite flooring for staircase,** treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification **- Ground Floor**	Sqmt	**4305.96**	Rupees Four Thousand Three Hundred Five Paise NinetySix Only

"DTS Approved"

Executive Engineer

C.E (R.R.N.)

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
134	27.40	Providing and laying **Hassan Green granite flooring for staircase,** treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification **- First Floor**	Sqmt	**4307.58**	Rupees Four Thousand Three Hundred Seven Paise FiftyEight Only
135	27.40	Providing and laying **Hassan Green granite flooring for staircase,** treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification - Second Floor	Sqmt	**4309.20**	Rupees Four Thousand Three Hundred Nine Paise Twenty Only
136	27.40	Providing and laying **Hassan Green granite flooring for staircase,** treads and rises using pre polished 20 mm thick water cut green Granite slab laid over existing cement concrete bed in CM 1:3, average 20mm thick including full rounding for nosing, cutting 3 line grooves not more than 2 mm wide for antiskidding, including cost of all materials, mortar, labour, curing etc., complete as per specification **- Third Floor**	Sqmt	**4310.82**	Rupees Four Thousand Three Hundred Ten Paise EightyTwo Only
137	274.30	Providing and laying flooring for **corridors/lobbies** using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and **preflamed 19mm** thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - **_do_ using 19mm thick granite width not less than 1200mm - Ground Floor**	Sqmt	**2760.48**	Rupees Two Thousand Seven Hundred Sixty Paise FourtyEight Only
138	52.50	Providing and laying flooring for **corridors/lobbies** using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and **preflamed 19mm** thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - **_do_ using 19mm thick granite width not less than 1200mm - First Floor**	Sqmt	**2762.10**	Rupees Two Thousand Seven Hundred SixtyTwo Paise Ten Only
139	52.50	Providing and laying flooring for **corridors/lobbies** using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and **preflamed 19mm** thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - **_do_ using 19mm thick granite width not less than 1200mm - Second Floor**	Sqmt	**2763.72**	Rupees Two Thousand Seven Hundred SixtyThree Paise SeventyTwo Only

"DTS Approved"

C.E (R.R.N.)

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
140	52.50	Providing and laying flooring for **corridors/lobbies** using combination of pre polished 19 mm thick water cut/gang saw Grey Granite, Black Granite, and strips of 50mm wide pre flamed grey granite using pre polished grey granite 19mm thick 76%, Pre polished black granite 19mm thick @ 2% and **preflamed 19mm** thick grey granite @22% over existing cement concrete bed in CM 1:4 average 20mm thick pointed with white cement/colour pigment etc., including cost of all materials, mortar, labour, curing etc., complete as per specification. - **_do_ using 19mm thick granite width not less than 1200mm - Third Floor**	Sqmt	**2765.34**	Rupees Two Thousand Seven Hundred SixtyFive Paise ThirtyFour Only
141	51.60	Providing and fixing **Vitrified glazed tiles** of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - Ground Floor	Sqmt	**1209.60**	Rupees One Thousand Two Hundred Nine Paise Sixty Only
142	492.10	Providing and fixing **Vitrified glazed tiles** of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification - **First Floor**	Sqmt	**1211.22**	Rupees One Thousand Two Hundred Eleven Paise TwentyTwo Only
143	337.30	Providing and fixing **Vitrified glazed tiles** of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification **- Second Floor**	Sqmt	**1212.84**	Rupees One Thousand Two Hundred Twelve Paise EightyFour Only
144	337.30	Providing and fixing **Vitrified glazed tiles** of approved make, quality & colour of size 600 x 600 x 10mm thick fixed on bed of 12mm thick cement mortar for flooring, skirting and jointed with neat cement slurry mixed with pigment to mach shade of tiles, including providing spacers at required interval and removing stains, including cost of all mateirals, mortar, labour, etc., Complete as per specification **- Third Floor**	Sqmt	**1214.46**	Rupees One Thousand Two Hundred Fourteen Paise FourtySix Only
145	102.00	Providing and fixing of wall cladding using 20mm thick gang saw water cut Shiva gold granite, grey granite in CM 1:3 proportion cut to required shape, pattern with paper joints, finished with cement mortal using white cement and colour pigments to match the colour of slab making through jointing with sealant, making holes 25mmx12mm grooves in joints including cost of all materials, mortar, labour, curing etc., complete as per specification.	Sqmt	**3809.16**	Rupees Three Thousand Eight Hundred Nine Paise Sixteen Only
146	60.00	Providing **full nosing for 20mm** thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification	Rmt	**257.04**	Rupees Two Hundred FiftySeven Paise Four Only
147	55.00	Providing half **nosing for 20mm thick** granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM of equipment etc., complete as per specification	Rmt	**170.64**	Rupees One Hundred Seventy Paise SixtyFour Only

"DTS Approved"

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
148	16.40	Providing **ceramic tiles** of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. **size 30x30cms - Ground Floor**	Sqmt	**1270.08**	Rupees One Thousand Two Hundred Seventy Paise Eight Only
149	15.30	Providing **ceramic tiles** of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. **size 30x30cms - First Floor**	Sqmt	**1271.70**	Rupees One Thousand Two Hundred SeventyOne Paise Seventy Only
150	9.30	Providing **ceramic tiles** of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. **size 30x30cms - Second Floor**	Sqmt	**1273.32**	Rupees One Thousand Two Hundred SeventyThree Paise ThirtyTwo Only
151	9.30	Providing **ceramic tiles** of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick cement mortor 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. **size 30x30cms - Third Floor**	Sqmt	**1274.94**	Rupees One Thousand Two Hundred SeventyFour Paise NinetyFour Only
152	156.00	KSRB 14-17.2: Providing skirting, dado, rises of steps with **colour glazed tiles** on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. **Ground Floor**	Sqmt	**1602.72**	Rupees One Thousand Six Hundred Two Paise SeventyTwo Only
153	117.40	KSRB 14-17.2: Providing skirting, dado, rises of steps with **colour glazed tiles** on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. **First Floor**	Sqmt	**1604.34**	Rupees One Thousand Six Hundred Four Paise ThirtyFour Only
154	78.50	KSRB 14-17.2: Providing skirting, dado, rises of steps with **colour glazed tiles** on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.**Second Floor**	Sqmt	**1605.96**	Rupees One Thousand Six Hundred Five Paise NinetySix Only
155	78.50	KSRB 14-17.2: Providing skirting, dado, rises of steps with **colour glazed tiles** on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications.-**Third Floor**	Sqmt	**1607.58**	Rupees One Thousand Six Hundred Seven Paise FiftyEight Only

"DTS Approved"

C.E (R.R.N.)

Executive Engineer

Contractor

157

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
156	180.00	Providing and laying heavy duty cobble stones 75mm thick inter lock pavers, using cement and course sand for manufacture of block of approved size, shape and colur with a minimum compressive strength of 281 Kg per Sqm over 50mm thick sand bed (average thickness) and compacting with plate vibrator having 3 tons compaction force thereby forcing part of sand underneath to come up in betwen joints, final compaction of paver surface joints its final level, including cost of materials, labour and HOM of machineries complete as per specification.	Sqmt	**1047.60**	Rupees One Thousand FourtySeven Paise Sixty Only
157	6.00	Providing and laying **Cinder concrete** in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - **First Floor**	Cumt	**2054.16**	Rupees Two Thousand FiftyFour Paise Sixteen Only
158	6.00	Providing and laying **Cinder concrete** in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - **Second Floor**	Cumt	**2054.16**	Rupees Two Thousand FiftyFour Paise Sixteen Only
159	6.00	Providing and laying **Cinder concrete** in cement 1:15 (1 cement: 15 cinder of 12.5mm nominal gauge) on terraced roof or sunken slabs, laid to slope compacting, including cost of materials, labour, curing complete as per specifications - **Third Floor**	Cumt	**2054.16**	Rupees Two Thousand FiftyFour Paise Sixteen Only
160	84.00	Providing **INTEGRAL CRYSTALINE Waterproofing treatment** to the sunken portion of toilets. Using Crystalline Slurry of approved make @ 1.40 kg per SQM in two coats (0.7 Kg per coat) confirming to ASTM S 1202 & DINV 18998 standards.	Sqmt	**518.40**	Rupees Five Hundred Eighteen Paise Fourty Only
161	450.00	Waterproofing of RCC Terrace / podium slab / toilet / utilities / water retaining structure by preparing the surface by chipping and cleaning and Grouting of Honey comb, voids,cracks / construction joints with cement slurry (1kg cement added in 10 ltr of water) added with 100gm of inorganic accelerator, followed by spraying of liquid biological modified alkaline earth silicates @ 0.40 ltr per sqm on whole surface to reduce the micro porosity and allowing it to dry, curing the surface for the silicates to penetrate deeper into the concrete and spraying waterproofing impregnate liquid containing silane and silanol linear copolymer @ 0.50 ltr per sqm and finally applying polymer slurry made out of cross linked acrylic / styrene / butadiene & cement in the ratio of 1:0.1, @0.50kg/sqm on the whole surface, including all labour charges tools and equipments, all complete as per the specification	Sqmt	**637.20**	Rupees Six Hundred ThirtySeven Paise Twenty Only
162	0.30	Providing **TEAK WOOD frames** of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications	Cum	**200787.12**	Rupees Two Lakh Seven Hundred EightySeven Paise Twelve Only
163	0.80	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - **Ground Floor**	Cum	**69034.68**	Rupees SixtyNine Thousand ThirtyFour Paise SixtyEight Only

"DTS Approved"

Contractor

C.E (R.R.N)

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
164	0.15	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - **First Floor**	Cum	**69034.68**	Rupees SixtyNine Thousand ThirtyFour Paise SixtyEight Only
165	0.15	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - **Second Floor**	Cum	**69034.68**	Rupees SixtyNine Thousand ThirtyFour Paise SixtyEight Only
166	0.15	Providing White Sal Wood frames of doors, windows, clerestory windows, and other frames, wrought, framed or assembledincluding making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications - **Third Floor**	Cum	**69034.68**	Rupees SixtyNine Thousand ThirtyFour Paise SixtyEight Only
164	4.80	KSRB 9.5-1 : Providing and fixing in position fully panelled Teak wood shutters for doors, with styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawingand panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No. KBS 9.34	Sqmt	**8964.00**	Rupees Eight Thousand Nine Hundred SixtyFour Only
165	24.80	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. - **Ground Floor**	Sqmt	**3313.44**	Rupees Three Thousand Three Hundred Thirteen Paise FourtyFour Only
166	6.30	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. - **First Floor**	Sqmt	**3313.44**	Rupees Three Thousand Three Hundred Thirteen Paise FourtyFour Only
167	6.30	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. - **Second Floor**	Sqmt	**3313.44**	Rupees Three Thousand Three Hundred Thirteen Paise FourtyFour Only
165	6.30	Providing and fixing flush door shutter made out of solid core black board type, well seasoned chemically treated hard wood battens and internal frame with minimum 45 mm wide wooden frame all-round door shutters covered with cross bonded wooden sheets (core veneer) hot pressed and fastened on both sides of the door using liquid phenol formaldehyde resin as per IS specification 2202 (Part-I) 1991. From manufacturer (Factory) complete as per specification. - **Third Floor**	Sqmt	**3313.44**	Rupees Three Thousand Three Hundred Thirteen Paise FourtyFour Only

"DTS Approved"

Contractor

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
166	**71.40**	Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - **Ground Floor**	Sqmt	**6696.00**	Rupees Six Thousand Six Hundred NinetySix Only
167	**41.00**	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - First Floor	Sqmt	**6701.40**	Rupees Six Thousand Seven Hundred One Paise Fourty Only

"DTS Approved"

C.E (R.R.N.

Executive Engineer

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
168	**41.00**	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar - Second Floor	Sqmt	**6706.80**	Rupees Six Thousand Seven Hundred Six Paise Eighty Only
166	**41.00**	KSRB 7.11 : Providing and fixing in position aluminium windows and ventilators as per approved drawings with sliding shutters using three track window frame of size 92x31.75mm bottom section 1.3mm thick,weight 1.07kg/m; sides and top sections 1.3 mm, thick, weight 0.933 kg/m.shutter frame section comprising top and bottom section of size 40mmx18mm, wall thickness 1.25mm. weight 0.417 kg./m. shutter side outer 40mm x 18mm. wall thickness 1.25mm. weight 0.417 kg/m, shutter interlock section 40mmx26.7mm wall thickness 1.1 mm. thick, weight 0.469 kg/m, the shutters mounted on nylon rollers with approved quality of fixtures such as aluminium handles tower bolts etc.; providing and fixing 5.5mm. thick plain glass for shutters fitted with rubber beading all aluminium sections including cutting to required length, joints mitred subdividing the frame tenonned and rivetted, in the assembled frame, stiffened with end clips for corners, angles etc., and fixed to the walls, lintels, floor beams/cills as the case may be, with necessary steel screws,raul plugs or teak wood gatties including cutting masonry or concrete and making good the original surface using cement mortar **- Third Floor**	Sqmt	**6712.20**	Rupees Six Thousand Seven Hundred Twelve Paise Twenty Only
167	3499.20	Providing and fixing **M.S.grill work for windows and ventilators** weighing 21 kg/sqm using M.S. flats, or M.S.square rods, or combination of M.S.flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifictions. Specification No. KBS 7.12 **(Considered 18 Kg/sqm)**	Kgs	**89.64**	Rupees EightyNine Paise SixtyFour Only
168	47.30	Providing and fixing in position **collapsible steel shutters** with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. Ground Floor	Sqmt	**4355.64**	Rupees Four Thousand Three Hundred FiftyFive Paise SixtyFour Only

"DTS Approved"

Executive Engineer

178

Sl No	Quantity	Description of work	Unit	Rate in Figures	Rate In Words
169	18.90	Providing and fixing in position **collapsible steel shutters** with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. **-First Floor**	Sqmt	**4361.04**	Rupees Four Thousand Three Hundred SixtyOne Paise Four Only
167	18.90	Providing and fixing in position **collapsible steel shutters** with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. **-Second Floor**	Sqmt	**4366.44**	Rupees Four Thousand Three Hundred SixtySix Paise FourtyFour Only
168	18.90	Providing and fixing in position **collapsible steel shutters** with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. **-Third Floor**	Sqmt	**4371.84**	Rupees Four Thousand Three Hundred SeventyOne Paise EightyFour Only
169	92.40	Providing and fixing **pull and push type rolling shutters** of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications.	Sqmt	**3090.00**	Rupees Three Thousand Ninety Only
170	39.90	Providing and fixing 65mmx90mm **GRP Doorframe** fabricatedusing E-Glass Chopped Strand Mat (CSM). U.V-stabilizedIsopthalic Gelcoat and Isopthalic resin. The thickness of the GRPskin shall not be less than 2.0 mm. The doorframe consists of foursegmens, which are providedwithplug-in-socket arrangementin-situ in the mould. The segments are plugged in and are joinedtogether by means of screws. The GRP frame shall be providedwith wooden reinforcement of 6 locations fro high screw holdingcapacity for fixing metallic hold fast and shall be consolidated byfilling with medium density foam/Plaster with fibre reinforcement.Six Numbers of 260mmx25mmx5mm size S shaped M.S. flat holdfast shall be provided with the frame - **Ground Floor**	Mtr	**518.40**	Rupees Five Hundred Eighteen Paise Fourty Only

" DTS Approved"

C.E (R.R.N.)

Executive Engineer